# ENTERPRISE FLEET TELEMATICS & RELIABILITY ANALYTICS: BUSINESS CASE & OPERATIONAL FINDINGS

**Author:** Jahnavi Sharma
**Role Target:** Fleet Data & Analytics Specialist / Reliability Data Scientist
**Domain Focus:** Caterpillar Heavy Equipment Telematics (VIMS / Product Link) & SAP Enterprise Asset Management (EAM)

---

## 1. PROJECT OVERVIEW

When running multi-million-dollar open-pit mining operations, keeping heavy machinery running isn't just an operational goal—it's what drives site profitability. Ultra-class Caterpillar fleets, including Cat 390F Excavators, 797F Haul Trucks, 994K Wheel Loaders, and D11 Dozers, work continuously under extreme conditions across remote site locations (Fort Hills, Kearl Oil Sands, Red Chris Mine, and Highvale Mine). Every single hour, onboard Caterpillar Product Link and VIMS hardware streams thousands of high-frequency IoT sensor pings tracking real-time engine health, line pressures, and fuel burn. At the exact same time, site technicians and shop supervisors log scheduled servicing, component swaps, and field repairs inside SAP Enterprise Asset Management (EAM).

In practice, these two worlds almost always operate in complete isolation. Telematics streams capture raw physical machine signals, while SAP logs rely on human-entered timestamps, work order stages, and component codes. When these datasets don't talk to each other, maintenance teams end up flying blind—relying on unverified uptime numbers and missing subtle warning signs before a major component fails.

To bridge this exact gap, this project delivers an Enterprise Fleet Telematics & Reliability Analytics Platform. By pairing a custom Python data engineering pipeline with an audited Power BI star-schema model, the platform automatically cleans sensor noise, reconciles active IoT telemetry against open SAP repair windows, and gives fleet leadership clear, data-backed visibility into physical availability, predictive failure risks, and overall fleet health.

---

## 2. STRATEGIC BUSINESS NEED & PROBLEM STATEMENT ("WHY?")

Operating heavy equipment fleets without integrated telematics and work-order reconciliation introduces severe operational and financial risks:

1. **Distorted Equipment Availability Reporting:** Unvalidated telemetry data and manual SAP work-order closure lags corrupt corporate reporting. When equipment remains marked as "In Maintenance" in SAP while actively operating and burning fuel in the pit, executives receive inaccurate Physical Availability figures.
2. **Unfiltered IoT Sensor Dropouts & Signal Noise:** Raw IoT feeds from remote mining pits frequently suffer from transmission loss, signal dropouts (-999 error codes), and unstandardized unit conventions (°F vs. °C, PSI vs. Bar). Relying on raw telemetry without an automated cleansing pipeline corrupts baseline health metrics and triggers false alarms.
3. **Reactive Maintenance & Unplanned Bottlenecks:** Traditional maintenance strategies react after a component fails or rely strictly on fixed hour-based servicing intervals. Without cross-analyzing multi-sensor thresholds (e.g., thermal coolant loads vs. hydraulic system pressure spikes), reliability teams miss subtle pre-failure signatures, turning minor seal leaks into catastrophic engine or pump replacements.
4. **Lack of Maintenance Traceability & Cost Leakage:** Without a standardized reconciliation loop, site managers cannot identify which component categories cause the longest repair delays or which mine locations exhibit systematic work-order logging delays.

---

## 3. CORE ANALYTICAL QUESTIONS & OBJECTIVES

The primary objective of the Fleet Reliability Dashboard is to establish a single source of truth across operations, maintenance engineering, and executive leadership. The interactive platform answers four core business questions:

| Core Business Question | Strategic Objective | Key Metric / Deliverable |
|---|---|---|
| **1. Data Integrity & Verification** | Reconcile active fuel burn against open SAP repair windows to flag discrepancies. | Audited Data Integrity Score (%) |
| **2. Operational Baselines** | Standardize dynamic calculations for key reliability indicators across all asset classes. | Physical Availability (%), MTBF, MTTR |
| **3. Predictive Anomaly Detection** | Map multi-sensor operating envelopes to isolate equipment near thermal limits. | Multi-sensor threshold alerts (°C vs. Bar) |
| **4. Maintenance Downtime Drivers** | Combine Pareto category breakdowns with AI Decomposition Trees to trace downtime. | Root-cause downtime path analysis |

---

## 4. DASHBOARD VISUAL ARCHITECTURE & INTERACTION SPECIFICATION

### 4.1 Page 1: Fleet Overview & Predictive Health (Executive & Operations View)

- 

| Dashboard Zone | Visual / Control Type | Field Bindings & Metrics | Technical Rule / Interaction Behavior |
|---|---|---|---|
| **Zone 1: Global Controls** | Header Banner & Slicers | dim_equipment[site_location], dim_equipment[asset_model], Dim_Calendar[Date] | Applies global filtering across all visual cards and plots on Page 1. |

| Dashboard Zone | Visual / Control Type | Field Bindings & Metrics | Technical Rule / Interaction Behavior |
|---|---|---|---|
| **Zone 2: Executive Banner** | KPI Card 1 | Fleet Physical Availability (%) = 93.14% | Evaluates total operating hours vs. available calendar hours (Green >= 92%, Amber 88–91.9%, Red < 88%). |
| **Zone 2: Executive Banner** | KPI Card 2 | Mean Time Between Failures (MTBF) = 136 Hours | Measures average operating runtime between unplanned work order events. |
| **Zone 2: Executive Banner** | KPI Card 3 | Mean Time To Repair (MTTR) = 11.67 Hours | Measures average shop duration required to resolve unplanned breakdown events. |
| **Zone 2: Executive Banner** | KPI Card 4 | Data Integrity Score (%) = 95.13% | Audited agreement percentage between active telemetry pings and SAP maintenance logs. |
| **Zone 3: Diagnostic Core** | Clustered Column Chart | X-Axis: Dim_Calendar[Date] Y-Axis: SUM(downtime_hours) Legend: site_location | Tracks daily unplanned downtime hours across mine sites. Clicking any site bar cross-filters the scatter plot and lower decomposition tree. |
| **Zone 3: Diagnostic Core** | Multivariate Scatter Plot | X-Axis: Average Hydraulic Pressure (Bar) (191.6–192.4) | Identifies machines near critical limits (> 90.2 °C coolant temp & > 192.3 Bar hydraulic |

| Dashboard Zone | Visual / Control Type | Field Bindings & Metrics | Technical Rule / Interaction Behavior |
|---|---|---|---|
| | | Y-Axis: Average Engine Temp (°C) (89.6–90.3)<br>Details: dim_equipment[equipment_id] | pressure) prior to catastrophic breakdown. |

---

### 4.2 Page 2: Maintenance Root-Cause & Governance Audit (Engineering & Audit View)

○

| Dashboard Zone | Visual / Control Type | Field Bindings & Metrics | Technical Rule / Interaction Behavior |
|---|---|---|---|
| **Zone 4: Root-Cause Analysis** | Horizontal Pareto Bar Chart | Y-Axis: parsed_component_category<br>X-Axis: Unplanned Downtime (Hours) | Displays downtime drivers (General Inspection, Drivetrain/Transmission, Engine System, Hydraulic System). Clicking a bar filters all visuals to that component. |
| **Zone 4: Governance Audit** | AI Decomposition Tree | Metric: Source Discrepancy Count (73 total)<br>Path: Site Location → Asset Model → Equipment ID | Traces telemetry active fuel burn (> 5 L/hr) during open SAP downtime work orders down to individual asset models and equipment IDs. |

---

# 5. KEY INSIGHTS, STRATEGIC RECOMMENDATIONS & IMPLEMENTATION ROADMAP

## 5.1 Deep Diagnostic Findings

An analysis of the reconciled Caterpillar telematics streams and SAP EAM work orders across the four active mine sites (Fort Hills, Kearl Oil Sands, Red Chris Mine, and Highvale Mine) revealed critical operational patterns and data governance bottlenecks:

### 1. Unplanned Downtime Drivers & Component Wear Trajectory

- **General Inspection & Drivetrain Predominance:** General Inspection activities and Drivetrain/Transmission repairs constitute over 65% of total unplanned fleet downtime hours across mining operations.
- **Component Wear Trajectory:** Drivetrain and Transmission issues represent the highest average repair duration per failure event (averaging 14.2 hours per incident), indicating that minor fluid degradation or thermal stress in torque converters and final drives are escalating into significant shop rebuilds rather than being caught during routine inspections.
- **Hydraulic System Volatility:** Hydraulic system failures account for fewer overall occurrences but exhibit rapid mean-time-to-repair spikes during extreme weather operations, pointing toward cold-temperature fluid cavitation.

### 2. Thermal-Hydraulic Stress & Predictive Anomaly Signatures

- **Predictive Operational Boundary:** Cross-analyzing continuous telematics feeds identified a clear pre-failure stress envelope. Machinery operating above 90.2C engine coolant temperature alongside hydraulic system pressures exceeding $192.3Bar$ exhibits higher probability of generating an unplanned SAP work order within 48 hours.
- **Component Fatigue Correlation:** Assets operating continuously near the upper thermal boundary showed accelerated hydraulic seal degradation, validating that real-time multi-sensor threshold monitoring can serve as an early warning indicator prior to catastrophic component breakdown.

### 3. Cross-System Data Discrepancies & Governance Audit

- **Site Discrepancy Breakdown:** Out of 73 total source discrepancy events flagged enterprise-wide, Kearl Oil Sands accounted for the largest share (35 instances), followed by Red Chris Mine (22 instances), Fort Hills (10 instances), and Highvale Mine (6 instances).
- **Root Cause of Discrepancies:** These discrepancies—where equipment registered active engine fuel burn ($> 5L/hr$) while officially logged under an open, active SAP repair work order—were driven primarily by administrative delays in closing out work orders after machinery returned to the pit, rather than unauthorized machine usage or physical equipment theft.

## 5.2 Strategic Recommendations

To transition site operations from reactive maintenance management to automated, data-driven fleet governance, three core initiatives are recommended:

1. **Implement Automated Telematics-Driven SAP Work Order Triggers:**
    - *Action:* Configure automated API webhooks between the Caterpillar Product Link/VIMS IoT gateway and SAP EAM.
    - *Impact:* Automatically trigger a "Maintenance Flag" inside SAP whenever an asset exceeds 90.0C engine coolant temperature and $192.0Bar$ hydraulic pressure simultaneously for more than 15 consecutive minutes, enabling proactive field inspection before catastrophic failure occurs.
2. **Mandate Geofenced Automated Work Order Closure:**
    - *Action:* Integrate GPS telematics geofencing around shop repair bays.
    - *Impact:* Systematically update SAP work order statuses from "In Progress" to "Pending Sign-off" as soon as an asset exits the shop perimeter and registers active fuel burn ($> 5L/hr$), eliminating the administrative lag responsible for the 35 discrepancy flags at Kearl Oil Sands.
3. **Standardize Asset Component Health Indexes:**
    - *Action:* Deploy the Data Integrity Score (%) DAX framework as a mandatory KPI across site operations dashboards.
    - *Impact:* Ensure site managers are evaluated not only on physical availability but also on data compliance, ensuring executive reporting relies on audited, high-integrity telemetry.

## 5.3 Strategic Implementation Roadmap

| Horizon | Phase | Key Deliverables & Milestones | Target Impact / Success Metric |
|---|---|---|---|
| **Phase 1** *(Months 1–2)* | **Data Pipeline Automation** | Convert Python ETL scripts into automated cloud functions (e.g., Azure Functions / Databricks) running hourly scheduled ingestions. | Eliminates manual data staging; standardizes metric conversions automatically. |

| | | | |
|---|---|---|---|
| **Phase 2** *(Months 3–4)* | **Automated Alerting & Push Notifications** | Build automated Power BI data alerts and Teams/Email notifications for thermal-hydraulic boundary breaches | Reduces MTTR by 15% by providing reliability engineers with instant pre-failure diagnostic context. |
| **Phase 3** *(Months 5–6)* | **Two-Way SAP Integration & Geofencing** | Establish bi-directional syncing between telematics fuel burn pings and SAP Work Order lifecycle stages via shop bay geofencing. | Sustains Data Integrity Score enterprise-wide and eliminates "ghost downtime" reporting error. |